

कार्यालय सहायक आयुक्त, देवस्थान विभाग खण्ड हनुमानगढ ।

क्रमांक- 694
प्रेषिति-

दिनांक - 15-6-2016


निदेशक,
सूचना एवं जनसम्पर्क निदेशालय,
राजस्थान सरकार, जयपुर ।

विषय- निविदा सूचना का प्रकाशन कराने बाबत ।

महोदय,

उपरोक्त विषय में निवेदन है कि इस कार्यालय के अधिनस्थ राजकीय प्रत्यक्ष प्रभार मन्दिरों की सामान्य मरम्मत व निर्माण कार्य के सम्बन्ध में इस कार्यालय की निविदा सूचना दिनांक 15.06.2016 संलग्न कर निवेदन है कि कृपया उक्त निविदा सूचना पत्र का प्रकाशन नियमानुसार हनुमानगढ में प्रचलित समाचार पत्र में एक राज्य स्तरीय समाचार पत्र के हनुमानगढ जिले के अंक में एवं एक स्थानीय समाचार पत्र में न्यूनतम साईज में आगामी प्रथम अंक में प्रकाशित कराने का श्रम करावें । निविदा सूचना प्रकाशन की एक प्रति इस कार्यालय में रिकार्ड हेतु भिजवाने का श्रम करावें ।


संलग्न - उपरोक्तानुसार


सहायक आयुक्त,
देवस्थान विभाग,
खण्ड हनुमानगढ

क्रमांक 695
प्रतिलिपी

दिनांक 15-06-2016

1. श्रीमान आयुक्त महोदय देवस्थान विभाग राजस्थान जयपुर को प्रेषित कर निवेदन है कि कृपया संलग्न निविदा सूचना विभागीय वेबसाईट पर अपलोड करवाने का श्रम करावें ।


सहायक आयुक्त,
देवस्थान विभाग,
खण्ड हनुमानगढ

कार्यालय सहायक आयुक्त देवस्थान विभाग हनुमानगढ ।

क्रमांक:—लेखा / मरम्मत / 2016—17 /

दिनांक 15.06.2016


निविदा सूचना

राजस्थान के राज्यपाल महोदय की ओर से निम्नानकित राजकीय मंदिरों के जीर्णोद्धार एवं मरम्मत एवं निर्माण कार्य हेतु सार्वजनिक निर्माण विभाग, केन्द्रीय सरकार, राज्य सरकार, या अन्य किसी अर्द्धराजकीय संस्थान में पंजीकृत ठेकेदारों से निर्धारित प्रपत्र में मुहरबन्द प्रतिशत निविदाएँ आमंत्रित की जाती है। इच्छुक निविदादाता निविदा प्रपत्र मय शर्तों के निर्धारित शुल्क 500/- जमा करवाकर दिनांक 4.07.2016 को प्रातः 11 बजे से सांय 6 बजे तक प्राप्त की जा सकती है तथा भरी हुई निविदा दिनांक 5.07.2016 को दोपहर 12 बजे तक जमा की जावेगी। प्राप्त निविदाएं उसी दिन 5.07.16 को दोपहर बाद 1.00 बजे उपस्थित निविदादाताओं के समक्ष खोली जावेगी। निविदा प्राप्त करने के लिए आवेदन पत्र के साथ पंजीकरण प्रमाण पत्र की सत्यापित छाया प्रति, बिल्टि कर कलियेरेन्स प्रमाण पत्र, सविस टैक्स पंजीकरण प्रमाण-पत्र की सत्यापित प्रति तथा पैन कार्ड की प्रति संलग्न की जानी आवश्यक होगी। अगर निर्धारित दिनांक को कोई अवकाश होता है तो निविदा आगामी कार्य दिवस में प्राप्त कर खोली जावेगी।

क्रमां.	कार्य का नाम	अनुमानित राशि(लाखों में)	धरोहर राशि	निविदा शुल्क	कार्य पूर्ण करने की अवधि
1	मंदिर श्रीजानकी वल्लभजी हनुमानगढ टाउन	4.32लाख	8640 /—	500 /—	3 माह

किसी भी निविदा को स्वीकार करने अथवा बिना कारण बताये अस्वीकार करने के समस्त अधिकार विभाग के पास सुरक्षित होंगे। निविदा सम्बन्धी शर्तें किसी भी कार्यदिवस में कार्यालय में देखी जा सकती है।

नोट:—उक्त निविदा सूचना देवस्थान विभाग की विभागीय वेबसाईट व sppportal पर भी देखी जा सकती है तथा निविदा प्रपत्र डाउनलोड कर सकते है।


सहायक आयुक्त
देवस्थान विभाग हनुमानगढ

मै० को जारी किया गया।

सहायक आयुक्त
देवस्थान विभाग हनुमानगढ़

कार्यालय सहायक आयुक्त देवस्थान विभाग खण्ड हनुमानगढ़ ।

1. कार्य का नाम:—
2. निविदा क्रमांक व दिनांक:— लेखा/मरम्मत/2016-17/ दिनांक 15.06.2016
3. निविदा शुल्क व दिनांक:— 500/-
4. निविदादाता फर्म का नाम व पता:—
.....
5. धरोहर राशि रूपये.....ड्राफ्ट सं.....दिनांक...../
बैंकर चैक सं..... दिनांक.....

हस्ताक्षर निविदादाता

Government of Rajasthan
Devasthan department
"G" Schedule

Last date of tender sale :	4-7-2016
Estimated cost :	4.32 Lac
Estimated money :	8640/-
Estimated time :	3 months
Estimated opening date :	5-7-2016
Estimated time period :	3 months

Work : Repair & Maintenance of Temple Shri Janki Balabh Ji Hanumangrath town

Code. PWD	Particulars	Quantity	Rate	Amount
14.25	Dismantling brick tiles covering in terracing including stacking of serviceable material and disposal of unserviceable material with in 50 meters	32.65 Sqm	22.00	718.30
14.3	Dismantling jack arch roofing and floors including stacking of serviceable material and disposal of unserviceable material with in 50 metter lead	32.65 Sqm	42.00	1371.30
14.7.3	Demolishing brick work including stacking of serviceable material and disposal of unserviceable material with in 50 meters lead. In cement mortar	9.60 Cum	339.00	3254.40
1.8	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trench or drain (not exceeding 1.5 M in width or 10 sum on plan) including dressing of sides and raming of bottoms, lift up to 1.5 m, including taking out the excavated soil and deposing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of meter. All kinds of material	20.70 Cum	159.00	3291.30
32.6	Providing and laying in position cement concrete including curing compaction etc. of specified grade excluding the cost of centering and shuttering = All up to plinth level: 1:3:6 (1 - Cement : 3 - Coarse sand : 6 - Graded stone aggregate 40 mm nominal size)	13.58 Cum	2909.00	39489.68
31.5	Brick masonry in foundation and plinth with bricks of class designation 75 imm in:1:4 (1 - Cement : 4 - Coarse sand)	7.92 Cum	2873.00	22754.16
35&	Brick masonry in superstructure up to third story with bricks of class designation 75 imm in 1:4 (1 - Cement : 4 - Coarse sand)	21.16 Cum	3084.00	65257.44
37.1	Supplying fixing stone lintels / bed plates of approved quarry rough dressed in cement mortar 1 : 4 : Up to 15 cm. thick	0.079 Cum	10427.00	823.73
32.2	Taking out decayed bricks from wall and replacing with new ones set : Cement sand mortar 1 : 6	150.00 Cum	236.00	35400.00

	Code. PWD	Particulars	Quantity	Rate	Amount
10	4.3.2	Reinforced cement concrete work in beams, suspended floors, roofs, girders having slopes up to 150, landings, balconies, shelves, chajjas, lintels, bands, plain windows sills, staircases and spiral staircases, up to floor three level including curing, compaction, finishing with rendering in cement sand mortar 1 : 3 (1 - Cement: 3 - Coarse sand) and making good and joints excluding the cost of centering, shuttering and reinforcement : 1 : 1 : 2 (1 - Cement : 1 - Coarse sand : 2 - Graded stone aggregate 20 mm nominal size)	14.35 Cum	3809.00	54655.34
11	4.12.2 (A)	Centering and shuttering with ply wood or steel sheets including Strutting, propping, bracing both ways with wooden members and removal of formwood for superstructure up to 4.5 mtr above plinth for : Suspended floors, roofs, landing, staircases, balconics, grids, cantilevers, bands, coping, bed plates, anchor blocks, sills, chhajjas, lintels, beam etc,	69.23 Cum	168.00	11630.64
12	4.13.3	Providing and fabricating reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) all compete up to floor three level. Hot rolled deformed bars (IS : 1139)	900.00 Kg	54.00	48600.00
13	11.35.2 (B)	Polished blue Kota stone slab flooring skirting, laid over 20 mm thick base of C.M 1 : 4 and jointed with grey cement slurry to match the shade of the slab including rubbing and polishing complete. for area of each slab up to 901 to 2000 Sq.cm(B) 30 mm thick slab	28.00 Cum	610.00	17080.00
14	12.9.2	Plaster on new surface on walls in cement sand mortar 1:6 including raking of joints etc. complete fine finish ; 20 mm thick.	92.00 Sqm	105.00	9660.00
15	13.4	Repair to cement plaster in cement mortar 1 : 6 (1 - Cement : 6 - fine sand) including removal of old plaster in regular shape and white or colour washing	300.00 Sqm	131.00	39300.00
16	6.13	Supplying and fixing in cement sand mortar 1 : 4 sand or other approved stone dassa or coping of thickness 75 to 100 mm (fine dressed : plain or bull nosed	5.29 Sqm	2290.00	12114.10

Code. PWD	Particulars	Quantity	Rate	Amount
17 9.2	Providing and fixing in position collapsible steel shutters with vertical M.S. Channels 20x10x2 mm and brackets with flat iron diagonals 20x5 mm, size with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys/ ball bearing complete with bolts, nuts locking arrangements inside and outside stoppers, handles etc. as per specification including applying a priming coat of approved steel primer. (To be measured and paid as per outer dimension).			
18 12.53	Finishing wall with water proofing cement paint of approved brand and manufacture and or required shade including all scaffolding :	7.50 Sqm	3336.00	25020.00
12.53.1	(a) New work (three or more coats)			
12.53.2	(b) Old work (two or more coats)	200.00 Sqm	35.00	7000.00
19 12.68.1	Painting with enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	800.00 Sqm	26.00	20800.00
	Total	349.60 Sqm	39.00	13634.40
				431854.79

3. Condatons :

1. All taxes what soever will be born by contractor.
2. Any extra item if executed at site shall be paid as per 2012 BSR rate forces plus or minus the tender premium.
3. Quantity of execution of item of works can be deceased or increased as per the condation of site
4. Contractor has to arrange at his own the prescribed competent authority for material procured and used by him own cost.
5. The work shall have to be completed with in specified time limts.
6. Any typographical mistake error commission in nomenclature of items and rates shall be corrected as per PWD B.S.R Hanumangrath Distt. 2012 building work.

Assistant Engineer
Devasthan Department Ja

Assistant Commissioner
Devasthan Department Bikaner
19766
above/below the " G " schedule.

I/We here by agree to execute the above work

Signature of contractor

Class.

Address :

Contact NO